



County of Fresno

DEPARTMENT OF PUBLIC WORKS AND PLANNING
STEVEN E. WHITE, DIRECTOR

August 23, 2021

Contract No. 21-02-C

ADDENDUM NO. 1 to LINCOLN AVENUE COLD PAVEMENT RECYCLING, revising the Plans as follows:

TABLE OF CONTENTS

No changes

NOTICE TO BIDDERS

DELETE:

2:00 P.M., (1400 hours and 00 seconds)
Thursday, August 26, 2021

REPLACE with:

3:30 P.M., (1530 hours and 00 seconds)
Thursday, August 26, 2021

DELETE:

LINCOLN AVENUE FROM SR 145 TO GRANTLAND ALIGN

FEDERAL PROJECT NUMBER: STPL 5942(300)

REPLACE with:

LINCOLN AVENUE FROM SR 145 TO FIG AVENUE

FEDERAL PROJECT NUMBER: CMLSTBG-5942(300)

DELETE:

The Federal minimum wage rates for this project as predetermined by the United States Secretary of Labor are set forth in **General Decision Number CA20210018, Dated 7/23/2021**, which is incorporated in these special provisions by this reference as if fully set forth herein and which can be viewed at <https://sam.gov>, under CA20210018. Said Federal wage rates, as well as project plans, special provisions, and bid forms, may also be examined at the County of Fresno office described in the preceding paragraph. Addenda to modify the reference to Federal minimum wage rates to reflect revisions thereto, if necessary, will be issued to planholders of record.

REPLACE with:

The Federal minimum wage rates for this project as predetermined by the United States Secretary of Labor are set forth in **General Decision Number CA20210018, Dated 8/13/2021**, which is incorporated in these special provisions by this reference as if fully set forth herein and which can be viewed at <https://sam.gov>, under CA20210018. Said Federal wage rates, as well as project plans, special provisions, and bid forms, may also be examined at the County of Fresno office described in the preceding paragraph. Addenda to modify the reference to Federal minimum wage rates to reflect revisions thereto, if necessary, will be issued to planholders of record.

BID ITEMS AND APPLICABLE SECTIONS

DELETE Aggregate Base

SPECIAL PROVISIONS

ADD to the end of Section 12-4.02C(3)(o):

The incomplete roadway may be opened to traffic. You are responsible for providing a safe, traversable surface during all construction operations including grading, repairs, ramping, and dust control. Payment for maintaining the temporary roadway is included in the other items of work.

REPLACE Section 19-9.02 with:

Material for shoulder backing may be RAP, native soil generated from roadway excavation, or import borrow from off site. Material shall be readily compactable, shall not contain deleterious materials, shall pass 100% through a 2-inch sieve, 20% to 40% passing the #200 sieve, a Plasticity Index less than 10, and shall provide a stable surface and uniform appearance as determined by the engineer.

REPLACE the last sentence in the first paragraph of Section 30-7.02D with:

RAP must be processed by mechanical means to pass the 1-inch sieve.

ADD to the end of Section 30-7.02D:

Imported Aggregate may be added to supplement the RAP quantity. Imported Aggregate must comply with the requirements of Section 26-1.02B Class 2 Aggregate Base and a maximum gradation of ¾-inch.

REPLACE item 2 in the list of items of Section 30-7.03C(2) with:

2. Have a cutter that can remove the existing pavement to the specified depths.

REPLACE item 2 in the list of items of Section 30-7.03D(7) with:

2. Add directly in the pugmill or mixing chamber dry or as a slurry.

PROPOSAL

DELETE Bid Item List - Proposal 2

REPLACE with the attached Proposal 2A

AGREEMENT

Project Limits

PROJECT DETAILS

No changes

PLANS

No changes

END OF ADDENDUM NO. 1

Please attach this Addendum to the inside cover of the Specifications booklet. If you have given the Bidding and Contract Documents to someone else, please forward this Addendum.



Aug 23, 2021

Date Signed

Supervising Engineer:

A handwritten signature in blue ink that reads "Joe Harrell". Below the signature, the text "Joseph C. Harrell, P.E." is printed in a small font.

Joseph C. Harrell, PE C80424

FRESNO COUNTY
Department of Public Works and Planning
m/a 2220 Tulare Street, Suite 720
Fresno, CA 93721-2106

Fresno County Department of Public Works and Planning

Bid Item List - Proposal 2.A

21-02-C

Description Lincoln Avenue Cold Pavement Recycling

Location Lincoln Ave From SR 145 to Fig Avenue

Project Items

Line Number	Item ID	Quantity	Unit	Unit Price	Total Price
Section: 1 SR145 - Grantland Alignment					
0010	1	130,000.000	\$	\$ 1.00	\$ 130,000.000
SUPPLEMENTAL WORK (PAYMENT ADJUSTMENT FOR PRICE INDEX FLUCTUATIONS)					
0020	2	1,000.000	\$	\$ 1.00	\$ 1,000.000
STATE WATER RESOURCES CONTROL BOARD NOTICE OF INTENT					
0030	3	1.000	LS	\$	\$
LEAD COMPLIANCE PLAN					
0040	4	2.000	EA	\$	\$
CONSTRUCTION PROJECT FUNDING SIGNS					
0050	5	1.000	LS	\$	\$
TRAFFIC CONTROL SYSTEM					
0060	6	2.000	EA	\$	\$
PORTABLE CHANGEABLE MESSAGE SIGN					
0070	7	1.000	LS	\$	\$
JOB SITE MANAGEMENT					
0080	8	1.000	LS	\$	\$
PREPARE STORM WATER POLLUTION PREVENTION PLAN					
0090	9	1.000	EA	\$	\$
STORM WATER ANNUAL REPORT					

Line Number	Item ID	Quantity	Unit	Unit Price	Total Price
0100	10	1.000	LS	\$	\$
DUST CONTROL PLAN					
0110	11	4.000	EA	\$	\$
REMOVE ROADSIDE SIGN					
0120	12	9,420.000	CY	\$	\$
ROADWAY EXCAVATION - FINAL PAY ITEM					
0130	13	13,362.000	CY	\$	\$
SHOULDER BACKING					
0140	14	3,729.000	CY	\$	\$
IMPORTED BORROW - FINAL PAY ITEM					
0150	15	1.000	LS	\$	\$
FINISHING ROADWAY					
0160	16	112,894.000	SQYD	\$	\$
MILLING (COLD CENTRAL PLANT RECYCLING)					
0170	17	43,747.000	TON	\$	\$
PROCESSING RAP (COLD CENTRAL PLANT RECYCLING)					
0180	18	482.000	TON	\$	\$
CEMENT (COLD CENTRAL PLANT RECYCLING)					
0190	19	1,204.000	TON	\$	\$
ASPHALT BINDER (CCPR - FOAMED ASPHALT)					
0200	20	43,747.000	TON	\$	\$
PLACE MAT (COLD CENTRAL PLANT RECYCLING)					
0210	21	9,956.000	TON	\$	\$
IMPORTED AGGREGATE					
0220	22	154.000	TON	\$	\$
ASPHALTIC EMULSION (COLD CENTRAL PLANT RECYCLING)					
0230	23	467.000	TON	\$	\$
SAND COVER (COLD CENTRAL PLANT RECYCLING)					

Line Number	Item ID	Quantity	Unit	Unit Price	Total Price
0240	24	23,467.000	TON	\$	\$
HOT MIX ASPHALT (TYPE A 3/4" GRADING)					
0250	25	485.000	TON	\$	\$
MINOR HOT MIX ASPHALT					
0260	26	2,734.000	SQYD	\$	\$
PLACE HOT MIX ASPHALT (MISCELLANEOUS AREAS)					
0270	27	74.000	TON	\$	\$
TACK COAT					
0280	28	7,930.000	SQYD	\$	\$
COLD PLANE ASPHALT CONCRETE PAVEMENT					
0290	29	4.000	EA	\$	\$
METAL MARKER POST					
0300	30	20.000	EA	\$	\$
SURVEY MONUMENTS (TYPE D)					
0310	31	8.000	EA	\$	\$
RELOCATE MAILBOX					
0320	32	4.000	EA	\$	\$
REMOVE PAVEMENT MARKER					
0330	33	20.000	EA	\$	\$
DELINEATOR (CLASS 1) (TYPE E)					
0340	34	50.000	EA	\$	\$
DELINEATOR (CLASS 1) (TYPE F)					
0350	35	4.000	EA	\$	\$
PAVEMENT MARKER					
0360	36	4.000	EA	\$	\$
OBJECT MARKER (TYPE P)					
0370	37	39,460.000	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 5)					

Line Number	Item ID	Quantity	Unit	Unit Price	Total Price
0380	38	2,705.000	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 18)					
0390	39	63.000	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 19)					
0400	40	84,330.000	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 27B)					
0410	41	200.000	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 27C)					
0420	42	533.000	SQFT	\$	\$
THERMOPLASTIC PAVEMENT MARKING					
0430	43	1.000	LS	\$	\$
MOBILIZATION					

Section 1 Total: \$

Line Number	Item ID	Quantity	Unit	Unit Price	Total Price
Section: 2 Grantland Alignment - Fig Ave					
0440	44	98,166.000	SQYD	\$	\$
COLD PLANE ASPHALT CONCRETE PAVEMENT					
0450	45	145.000	CY	\$	\$
REPLACE ASPHALT CONCRETE PAVEMENT					
0460	46	6,160.000	CY	\$	\$
SHOULDER BACKING					
0470	47	2,406.000	CY	\$	\$
IMPORTED BORROW					
0480	48	8.000	EA	\$	\$
SURVEY MONUMENTS (TYPE D)					
0490	49	18,923.000	TON	\$	\$
HOT MIX ASPHALT (TYPE A 3/4" GRADING)					

Line Number	Item ID	Quantity	Unit	Unit Price	Total Price
0500	50	381.000	TON	\$	\$
MINOR HOT MIX ASPHALT					
0510	51	2,150.000	SQYD	\$	\$
PLACE HOT MIX ASPHALT (MISCELLANEOUS AREAS)					
0520	52	31.000	TON	\$	\$
TACK COAT					
0530	53	77,440.000	SQYD	\$	\$
PAVING FABRIC					
0540	54	26,803.000	EA	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 5)					
0550	55	7,220.000	EA	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 18)					
0560	56	228.000	SQFT	\$	\$
THERMOPLASTIC PAVEMENT MARKING					
0570	57	1.000	LS	\$	\$
MOBILIZATION					
Section 2 Total:					\$
Project Total:					\$