


ADDENDUM 03

Contract # 21-S-01

Dated: 04-11-2022

The foregoing documents are amended in the respects as herein set forth. This addendum and the amendments herein shall become part of said documents and of any contract entered into pursuant to said documents.

PLEASE ACKNOWLEDGE THIS ADDENDUM ON YOUR PROPOSAL. IF YOU HAVE GIVEN THE CONTRACT DOCUMENTS TO SOMEONE ELSE, PLEASE FORWARD THIS ADDENDUM.



04.11.2022

Date Signed

Architect of Record:

Office: (559) 600-4477
ndavidson@fresnocountyca.gov

Noel Roger Davidson II, #C27818
License Renewal 10/31/23

**Fresno County Department of Public Works and Planning
Development Services & Capital Projects Division**
2220 Tulare Street, 8th Floor
Fresno, CA 93721-2104

A. BID FORMS AND CONTRACT CONDITIONS: None at this time

B. SPECIFICATIONS: None at this time

C. DRAWINGS:

a. E1 – Single Line Diagram: The following keynotes have been revised to clarify Owner furnished, Contractor Installed items:

- i. Revise Keynote #1 to:** "TOSHIBA G9000 BATTERY CABINET FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR."
- ii. Revise Keynote #2 to:** "TOSHIBA G9000 UPS FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR. FACTORY STARTUP BY MANUFACTURER. PROVIDE COMMON CONCRETE PAD FOR 225kVAUPSs, BATTERY CABINETS, AND TIE CABINET."
- iii. Revise Keynote #7 to:** "DIESEL GENSET FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR. PROVIDE LOAD SIDE FEEDER AND CONNECTIONS FOR BATTERY CHARGER, JACKET HEATER, ALTERNATOR WINDING HEATER AND 2 STATUS MONITORING PANELS AND ETHERNET MODULES."
- iv. Revise Keynote #8 to:** "2000 AMP, 4-POLE AUTOMATIC TRANSFER SWITCH FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR. FREESTANDING NEMA 1 ENCLOSURE, PROVIDE CONCRETE PAD."
- v. Revise Keynote #9 to:** "TOSHIBA G9000 UPS FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR. FACTORY STARTUP BY MANUFACTURER. PROVIDE COMMON CONCRETE PAD FOR 225kVAUPSs, BATTERY CABINETS, AND TIE CABINET."
- vi. Revise Keynote #10 to:** "TOSHIBA TIE CABINET FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR. INSTALL OWNER PROVIDED SQUARE D "I-LINE", FREESTANDING DISTRIBUTION BOARD AND CONCRETE PAD. PROVIDE COMMON CONCRETE PAD FOR UPSs, BATTERY CABINETS, AND TIE CABINET."
- vii. Revise Keynote #11 to:** "INSTALL OWNER PROVIDED SQUARE D "I-LINE", FREESTANDING SWITCHBOARD. PROVIDE CONCRETE PAD."
- viii. Revise Keynote #12 to:** "PROVIDE CONCRETE PAD AND INSTALL OWNER FURNISHED SOLA-HD K-20 RATED TRANSFORMERS."
- ix. Revise Keynote #14 to:** "ONYX POWER DISTRIBUTION UNITS FURNISHED BY OWNER AND INSTALLED BY CONTRACTOR."
- x. Revise Keynote #19 to:** "PROVIDE CONCRETE PAD AND INSTALL OWNER FURNISHED SOLA-HD K-20 RATED TRANSFORMER."

D. GENERAL CLARIFICATIONS: None at this time

END OF ADDENDUM 03