



# County of Fresno

DEPARTMENT OF PUBLIC WORKS AND PLANNING  
STEVEN E. WHITE, DIRECTOR

September 27, 2022

Contract No. 22-14-C

**ADDENDUM NO. 3** to Golden State Boulevard Phase 1 revising the Bidding and Contract Documents and Plans as follows:

## **TABLE OF CONTENTS**

No changes

## **NOTICE TO BIDDERS**

No changes

## **SPECIAL PROVISIONS**

**ADD** The 2nd and 3rd paragraphs of section 5-1.20E:

The Contractor will install the water meters. Install 2" water meters per City of Fresno Std plan W-1 or equal as approved by the Engineer.

The Contractor charges for:

1. Furnishing and installing each water meter
2. Connecting to the local water authority's main water line, including any required hot tap or tee
3. Furnishing and installing an extension pipe from the main water line to the water meter
4. Sterilizing the extension pipe

## **PROPOSAL**

**DELETE** Bid Item List - Proposal 2A

**REPLACE** with: the attached Bid Item List - Proposal 2B

## **PLANS**

### **DELETE:** Plans:

Region 1: Sheet No 15, 37A & 38A

Region 2: Sheet No 3 & 153

### **REPLACE with:** Plans:

Region 1: Sheet No 15A, 37B & 38B

Region 2: Sheet No 3A & 153A

## **Region 2 Sheet No. 1**

### **DELETE:**

Contract No. 21-14-C

### **REPLACE with:**

Contract No 22-14-C

## **END OF ADDENDUM NO. 3**

-----  
Please attach this Addendum to the inside cover of the Specifications booklet. If you have given the Bidding and Contract Documents to someone else, please forward this Addendum.

Date Signed: 9/27/2022

Consultant Engineer: \_\_\_\_\_



Ed Noriega, PE C61555

MARK THOMAS  
7571 North Remington Ave., Suite 102  
Fresno, CA 93711





9/27/2022

\_\_\_\_\_  
Date Signed

**Supervising Engineer:**

A handwritten signature in blue ink, appearing to be "S. Artal", written over a horizontal line.

\_\_\_\_\_  
Sebastian Artal, PE C76724

FRESNO COUNTY  
**Department of Public Works and Planning**  
m/a 2220 Tulare Street, Suite 720  
Fresno, CA 93721-2106

# Fresno County Department of Public Works and Planning

## Bid Item List - Proposal 2B

Contract # 22-14-C

Contract Name

Golden State Boulevard Phase 1

Location

American Avenue to Mission Street

### Bid Items

Item ID	Quantity	Unit	Unit Price	Total
1	1	LS	\$	\$
Lead Compliance Plan				
2	250,000	\$	\$	\$ 250,000.00
Compensation for Adjustments for Price Fluctuations				
3	500,000	\$	\$	\$ 500,000.00
Supplemental Work				
4	1	LS	\$	\$
Mobilization				
5	1	LS	\$	\$
Furnish Field Office				
6	2	EA	\$	\$
Construction Project Funding Sign				
7	1	LS	\$	\$
Temporary Traffic Control				
8	1	LS	\$	\$
Job Site Management				
9	1	LS	\$	\$
Prepare Storm Water Pollution Prevention Plan				

Item ID	Quantity	Unit	Unit Price	Total
10	27	EA	\$	\$
Rain Event Action Plan				
11	1	LS	\$	\$
SWPPP Implementation				
12	17	EA	\$	\$
Storm Water Sampling and Analysis Day				
13	1,000	EA	\$	\$ 1,000.00
State Water Resources Control Board NOI Filing Fee				
14	1	EA	\$	\$
Storm Water Annual Report				
15	1	LS	\$	\$
Dust Control Plan				
16	2	EA	\$	\$
Relocate Fire Hydrant				
17	10	EA	\$	\$
Adjust Utility Box to Grade				
18	83	EA	\$	\$
Adjust Valve Box Frame and Cover to Grade				
19	1	CY	\$	\$
Remove Concrete Valley Gutter				
20	500	LF	\$	\$
Temporary High-Visibility Fence (Type ESA)				
21	87	EA	\$	\$
Remove Tree				
22	1	LS	\$	\$
Clearing and Grubbing				

Item ID	Quantity	Unit	Unit Price	Total
23	23,600	CY	\$	\$
Roadway Excavation - Final Pay Item				
24	9,000	CY	\$	\$
Roadway Excavation (Type Z-2) (Aerially Deposited Lead) - Final Pay Item				
25	12,200	CY	\$	\$
Aggregate Base (Class II) - Final Pay Item				
26	269,000	SF	\$	\$
Full Depth Reclamation - Cement (FDR-C)				
27	16,800	SY	\$	\$
Crack and Seat				
28	60	TON	\$	\$
Slurry Seal				
29	59,800	TON	\$	\$
Hot Mix Asphalt (Type A)				
30	2,170	TON	\$	\$
Rubberized Hot Mix Asphalt				
31	217,000	SY	\$	\$
Stress Absorbing Membrane Interlayer				
32	130	TON	\$	\$
Tack Coat				
33	620	LF	\$	\$
Place Hot Mix Asphalt Dike (Type A)				
34	45	LF	\$	\$
Place Hot Mix Asphalt Dike (Type D)				
35	140	LF	\$	\$
Place Hot Mix Asphalt Dike (Type E)				

Item ID	Quantity	Unit	Unit Price	Total
36	190	LF	\$	\$
Place Hot Mix Asphalt Dike (Type F)				
37	620	LF	\$	\$
Remove HMA Dike				
38	246,800	SY	\$	\$
Cold Plane Asphalt Concrete Pavement				
39	248,000	SY	\$	\$
Cold In-Place Recycling				
40	1,450	CY	\$	\$
Remove Base and Surfacing - Final Pay Item				
41	3,490	CY	\$	\$
Remove Concrete Pavement and Base - Final Pay Item				
42	4	EA	\$	\$
COK Manhole (Type A)				
43	2	EA	\$	\$
City of Selma Inlet (Std SD-3)				
44	2	EA	\$	\$
COK Curb Inlet				
45	59	LF	\$	\$
12" Reinforced Concrete Pipe				
46	640	LF	\$	\$
18" Reinforced Concrete Pipe				
47	430	LF	\$	\$
24" Reinforced Concrete Pipe				
48	2	EA	\$	\$
18" Steel Flared End Section				



Item ID	Quantity	Unit	Unit Price	Total
49	1	EA	\$	\$
Inlet (Type GMP Steel Pipe)				
50	1	EA	\$	\$
Drainage Inlet (Type G1)				
51	1	EA	\$	\$
Abandon Pipe				
52	30	LF	\$	\$
Remove Storm Drain				
53	1	EA	\$	\$
Remove Inlet				
54	2	EA	\$	\$
Remove OMPI Inlet				
55	2	EA	\$	\$
Remove Headwall				
56	86	EA	\$	\$
Adjust Manhole to Grade				
57	7	CY	\$	\$
Rock Slope Protection (Class II, Method B)				
58	20	SY	\$	\$
Rock Slope Protection Fabric (Class 8)				
59	1,820	SF	\$	\$
Detectable Warning Surface				
60	8,930	LF	\$	\$
Minor Concrete - Median Curb				
61	70	LF	\$	\$
Minor Concrete - Valley Gutter				

Item ID	Quantity	Unit	Unit Price	Total
62	200	LF	\$	\$
Minor Concrete - Valley Gutter (Modified)				
63	10,900	LF	\$	\$
Minor Concrete - Curb and Gutter				
64	740	LF	\$	\$
Minor Concrete - Retaining Curb				
65	790	SY	\$	\$
Minor Concrete - Driveway				
66	320	SY	\$	\$
Minor Concrete - Stamped Concrete				
67	4,000	SY	\$	\$
Minor Concrete - Sidewalk				
68	85	CY	\$	\$
Minor Concrete -Curb Ramp				
69	10,100	LF	\$	\$
Remove Concrete Curb				
70	5,020	LF	\$	\$
Remove Concrete Curb and Gutter				
71	3,060	SY	\$	\$
Remove Concrete Sidewalk				
72	40	LF	\$	\$
Chain Link Fence (Type CL-6)				
73	54	EA	\$	\$
Remove Roadside Sign				
74	44	EA	\$	\$
Relocate Roadside Sign				

Item ID	Quantity	Unit	Unit Price	Total
75 Roadside Sign	95	EA	\$	\$
76 Midwest Guardrail System (Wood Post)	8,510	LF	\$	\$
77 Strengthened Midwest Guardrail System	41	LF	\$	\$
78 End Anchor Assembly (Type SFT)	108	EA	\$	\$
79 Alternative Flared Terminal System	108	EA	\$	\$
80 4" White 2-Coat Paint Traffic Striping (Detail 8, 12,27B)	49,700	LF	\$	\$
81 6" White 2-Coat Paint Traffic Striping (Detail 39, 39A)	195,000	LF	\$	\$
82 4" Yellow 2-Coat Paint Traffic Striping (Detail 21, 22, 24, 25 29, 31, 32)	25,000	LF	\$	\$
83 4" White Thermoplastic Traffic Striping (Detail 12, 27B)	23,300	LF	\$	\$
84 4" Yellow Thermoplastic Traffic Striping (Detail 21, 25, 27, and 35A)	22,300	LF	\$	\$
85 8" White 2-Coat Paint Traffic Striping (Detail 38, 38A, Chevron Striping)	3,760	LF	\$	\$
86 8" Yellow 2-Coat Paint Traffic Striping (Chevron Striping)	350	LF	\$	\$
87 8" White Thermoplastic Traffic Striping (Detail 37, 38, 38A and Chevron Striping)	1,340	LF	\$	\$

Item ID	Quantity	Unit	Unit Price	Total
88	890	LF	\$	\$
8" Yellow Thermoplastic Traffic Striping (Chevron Striping)				
89	20,700	SF	\$	\$
Thermoplastic Pavement Marking				
90	30,200	LF	\$	\$
6" Yellow 2-Coat Paint Traffic Striping Detail				
91	7,560	SF	\$	
Green Paint Pavement Marking				
92	640	SF	\$	\$
2-Coat Paint Pavement Marking				
93	17,151	LF	\$	\$
Trenching/Conduit				
94	43,634	LF	\$	\$
Conductors - #6				
95	13,930	LF	\$	\$
Conductors - #8				
96	195	LF	\$	\$
Conductors - #2				
97	4	EA	\$	\$
Foundations - Potholing				
98	4	EA	\$	\$
Street Lighting - Foundations - Type III-CF (TESCO 26-100) Service Enclosure				
99	4	EA	\$	\$
Street Lighting - Foundations - Mast Arm Poles				
100	64	EA	\$	\$
Street Lighting - Foundations - 15TS Poles				

Item ID	Quantity	Unit	Unit Price	Total
101	1	EA	\$	\$
Street Lighting - Foundations - 15D Poles				
102	45	EA	\$	\$
Street Lighting - Foundations - Ornamental Light Poles				
103	132	EA	\$	\$
Street Lighting - Pull Boxes - No.3 1/2				
104	1	EA	\$	\$
Street Lighting - Pull Boxes - No. 5E with Extension				
105	1	EA	\$	\$
Street Lighting - Pull Boxes - No. 5E with Extension & 12" Concrete Collar				
106	7	EA	\$	\$
Street Lighting - Pull Boxes - No. 6E with Extension				
107	8	EA	\$	\$
Street Lighting - Pull Boxes - PG&E Approved No. 2 PB				
108	1	LS	\$	\$
Street Lighting - Installed and Spliced				
109	1	EA	\$	\$
Street Lighting - Poles - 17-3-100, No Mast Arm				
110	1	EA	\$	\$
Street Lighting - Poles - 24-3-100, No Mast Arm				
111	2	EA	\$	\$
Street Lighting - Poles - 26-3-100, No Mast Arm				
112	41	EA	\$	\$
Street Lighting - Poles - 15TS				
113	1	EA	\$	\$
Street Lighting - Poles - 15D				

Item ID	Quantity	Unit	Unit Price	Total
114	45	EA	\$	\$
Street Lighting - Poles - Decorative Pole				
115	47	EA	\$	\$
Street Lighting - Signal Hardware - Luminaires				
116	90	EA	\$	\$
Street Lighting - Signal Hardware - Decorative Luminaires				
117	4	EA	\$	\$
Street Lighting - Control - Type III-AF (TESCO 26-100) Service Enclosure				
118	4	EA	\$	\$
Street Lighting - Demolition - Remove Pull Boxes				
119	1	EA	\$	\$
Street Lighting - Demolition - Remove PG&E Pole and Service Wire				
120	7	EA	\$	\$
Street Lighting - Demolition - Remove Luminaires				
121	1	EA	\$	\$
Street Lighting - Demolition - Remove PG&E Luminaire				
122	9	EA	\$	\$
Street Lighting - Demolition - Remove Street Light with Foundation				
123	1	LS	\$	\$
Signal Modifications (Floral Avenue at Whitson Street)				
124	1	LS	\$	\$
Signal Modifications (Thompson Avenue at Whitson Street)				
125	1	LS	\$	\$
Signal Modifications (Golden State Blvd at San Antonio Drive )				
126	1	LS	\$	\$
Signal Modifications (Golden State Blvd at Jug Handle to Clovis Avenue)				

Item ID	Quantity	Unit	Unit Price	Total
127	1	LS	\$	\$
Service Irrigation				
128	15,294	EA	\$	\$
Packet Fertilizer				
129	2,513	EA	\$	\$
Plant (Group A)				
130	768	EA	\$	\$
Plant (Group B)				
131	435	EA	\$	\$
Plant (Group U)				
132	1	LS	\$	\$
Plant Establishment Work				
133	761	CY	\$	\$
Wood Mulch				
134	4,217	LF	\$	\$
Root Barrier				
135	1	LS	\$	\$
Control And Neutral Conductors				
136	18	EA	\$	\$
1" Remote Control Valve				
137	4	EA	\$	\$
2" Remote Control Valve				
138	4	EA	\$	\$
Two-Wire Irrigation Controller				
139	55,596	LF	\$	\$
5/8" Drip Irrigation Tubing - Final Pay Item				

Item ID	Quantity	Unit	Unit Price	Total
140	4	EA	\$	\$
Irrigation Controller Enclosure Cabinet				
141	4	EA	\$	\$
2" Backflow Preventer Assembly				
142	4	EA	\$	\$
Backflow Preventer Enclosure				
143	4	EA	\$	\$
Backflow Preventer Blanket				
144	4	EA	\$	\$
Flow Sensor				
145	932	EA	\$	\$
Tree Well Sprinkler Assembly				
146	18	EA	\$	\$
Drip Valve Assembly				
147	4	EA	\$	\$
1" Gate Valve				
148	10,757	LF	\$	\$
3/4" Plastic Pipe (Schedule 40) (Supply Line) - Final Pay Item				
149	1,402	LF	\$	\$
1" Plastic Pipe (Schedule 40) (Supply Line) - Final Pay Item				
150	1,059	LF	\$	\$
1 1/4" Plastic Pipe (Schedule 40) (Supply Line) - Final Pay Item				
151	571	LF	\$	\$
1 1/2" Plastic Pipe (Schedule 40) (Supply Line) - Final Pay Item				
152	8,410	LF	\$	\$
2" Plastic Pipe (Schedule 40) (Supply Line) - Final Pay Item				



Item ID	Quantity	Unit	Unit Price	Total
153	2,111	LF	\$	\$
6" Plastic Pipe (Class 315) (Supply Line) - Final Pay Item				
154	16	EA	\$	\$
Ball Valve				
155	114	CY	\$	\$
Concreted-Rock Slope Protection (Cobble, Method A) (Cy) - Final Pay Item				
156	20	EA	\$	\$
Survey Monuments				
157	1,340	STA	\$	\$
Shoulder Backing				
158	15	EA	\$	\$
City of Fresno Bollard				
159	1	LS	\$	\$
Replace Traffic Loop Detectors (Sierra St)				
160	6	EA	\$	\$
Portable Changeable Message Sign				
161	4	EA	\$	\$
2" Water Meter				
162	38,100	TON	\$	\$
Hot Mix Asphalt (Type A) 1/2"				

Bid Items Total: \$